

Bulson Creek

2010 Skagit Watershed

Before Project



After Project – during high water event



Project Description

This project was completed by both the Natural Resource Stewardship Program and an additional grant of \$50,000 from the National Fish and Wildlife Federation and consisted of three landowners. Bulson Creek was eroding towards an operational dairy farm and in an effort to minimize the possibility of fecal coliform inputs while also reducing erosion towards the barn Skagit County re-routed almost 400 feet of the creek. During this process the County installed 12 large woody debris structures to increase channel complexity for fish. The County installed almost 2,400 native plants and removed blackberry along 640 linear feet of stream. A large portion of the project area was enrolled in the Conservation Reserve Enhancement Program (CREP) and this area is not reflected in our totals. The area will be under on-going maintenance until 2012.

Vicinity Map

