

ADDENDUM NO. 1

May 5, 2020

Maddox Creek Restoration Project #WA402227

NOTICE TO PROSPECTIVE BIDDERS

NOTICE IS HEREBY GIVEN BY SKAGIT COUNTY that the Contract Provisions and Plans have been modified as follows:

- 1. Pg. 36, Section 1-06.2 Acceptance of Materials lines 27-28 are modified to read:**
...samples of the Type 1 and Type 2 large wood material (LWM) (§8-28.2.2), stream bed boulders and gravel and cobble stream bed mix (§9-03.11) that it...
- 2. Pg. 45, Section 8-01.3(1)A1 Temporary Erosion and Sediment Control Plan, lines 15 through 16 are modified to read:**
...and protect off-site waterbodies from sediment runoff. Specific BMPs are listed in Sheet 12 "Work Sequencing and Temporary Erosion and Sediment Control (TESC) Measures"...
- 3. Pg. 45, Section 8-01.3(9) Sediment Control Barriers, lines 37 and 38 are modified to read:**
Other TESC BMPs, including but not limited to installation of straw wattles and hydroseeding, shall be done per the specifications in Section 8-01.3. All straw shall be certified weed free. Contractor shall provide manufacturer's satisfactory test report and certification of compliance prior to use in the project.
- 4. Pg. 47, Section 8-05.2 Specific BMPs and Materials, line 18 is modified to read:**
...specific BMPs that are identified in Sheet 12 "Work Sequencing and TESC measures" of...
- 5. Pg. 49, Section 8-19.2 Materials the last sentence is removed.**
The Contractor shall submit samples of the willow cuttings to the Contracting Agency for approval at least ten days prior to use.
- 6. Pg. 49, Section 8-19.2 Materials, sub-section Fill Soils, line 37 is modified to read:**
... Common Borrow. Topsoil shall meet the requirements of Section 9-14.1(1) "Topsoil..."
- 7. Pg. 50, Section 8-19.2 Materials, sub-section Willow cuttings, lines 15 and 16 are modified to read:**
Cuttings will be provided by the Contracting Agency 1-business day before installation, excluding Friday. One week notice of scheduling is required.
- 8. Sheet 10– Channel and LWM Specifications**
 - Gravel and Cobble Stream Bed Mix
 - Item 3 is modified to read: "The boulders are 18" to 24" mean diameter and will be provided by the Contractor".

9. Sheet 12 – Work Sequencing and TESC BMPs

- Erosion Control Planting and Site Cleanup
 - Remove item 7.6

10. Schedule of Measurement and Payment for Specific Bid Items

- Item 3 Traffic Control
Remove as required by the City of Mount Vernon road access permit.

11. Engineer's Estimate

\$550,000 - \$700,000

12. Appendix E – Proposal Packet – Informational Only

Replace Maintenance of Restoration Projects in Skagit County with Maddox Creek Culvert Removal Project #WA402227

END OF ADDENDUM No. 1

**THIS ADDENDUM MUST BE ACKNOWLEDGED BY SIGNATURE ON
THE REVISED PROPOSAL PACKET DATED MAY 5, 2020**

DATE OF BID OPENING: June 1, 2020 at 2:45 p.m.



Emily Derenne
Project Manager



Michael See
Natural Resource Division Manager