

ADDENDUM NO. 3A

May 26, 2020

**Maddox Creek Restoration Project
#WA402227**

NOTICE TO PROSPECTIVE BIDDERS

NOTICE IS HEREBY GIVEN BY SKAGIT COUNTY that the Contract Provisions and Plans have been modified as follows:

1. Pgs 138-139. Schedule of Measurement and Payment

Removed and replaced with:

Item No.	Item	Basis of payment	WSDOT Standard Spec. Section	Description/Specification
1	Submittals: Work plan, SPCC, traffic control and dewatering plans	lump sum	8-01.3(1)A, as applicable.	Cost for preparing the required work plan , spill prevention control and countermeasures (SPCC) plan, and construction site dewatering/stream isolation plan, as required by the construction permits.
2	Mobilization and demobilization	lump sum		Cost for mobilization and demobilization of all materials, equipment, contractor facilities and labor.
3	Traffic control	days	1-10.2	Cost for implementing the approved plan for ensuring traffic safety in vicinity of the work site, as required by the City of Mount Vernon road access permit (Permit removed per Addendum 1.)
4	Stabilized construction entrance and SPCC facilities	lump sum	8-01.3(7)	Equipment and supplies for implementing contractor's SPCC plan; angular rock, mud removal pad or equivalent for removing mud from tires and protecting pavement and curbs at the entrance to the work site.
5	Stream isolation and install dewatering pumps	lump sum	Spec. Prov. 8-05	Cost for furnishing and installing BMPs to isolate the worksite from flowing water and to dewater the work site if needed. Includes costs for staging dewatering pumping. Costs for running the pump(s) will be paid from the contracting agency's force account, if needed. Fish exclusion will be done by the Contracting Agency and is not included in the bid.
6	High visibility construction fencing	lineal feet	8-01.3(9)A1	Furnish and install high-visibility plastic mesh fencing at sensitive areas to be demarcated by the site manager. Additional installation may be needed per environmental permits.
7	Clearing, grubbing and tree salvage	acre	2-01, Spec. Prov. 2-03.3(10)	Vegetation clearing and grubbing from area flagged by the site manager. Cleared vegetation to be disposed off site except trees flagged by the site manager for subsequent use in Bid Items 18 (Type 3 LWM).
8	Common excavation	cubic yards	1-09 as applicable	Cost for all excavation, including culvert overburden removal, hill slope grading, and stream channel and drainage swale grading. Quantity measured in place.

Item No.	Item	Basis of payment	WSDOT Standard Spec. Section	Description/Specification
9	Culvert demolition and disposal	lump sum	Spec. Prov. 2-02	Cost for labor, equipment and disposal fees for removing the existing culvert and disposing it at an off-site disposal facility
10	Culvert trench backfill and compaction (Structural excavation Class B)	cubic yards	2-09.3(4)	Cost for backfilling the culvert excavation trench with clean borrow soil and grading and compacting per the plan details.
11	Soil disposal - haul offsite (primary site)	cubic yards	2-04	Cost for hauling the excavated culvert overburden material and disposing it at an offsite location approved by the contracting agency. Quantity measured in place.
*11 ¹	Soil disposal - haul offsite (alternate site)	cubic yards	2-04	Cost for hauling the excavated culvert overburden material and disposing it at an offsite location approved by the contracting agency. Contractor shall provide equipment for management of stockpiled material. Quantity measured in place.
12	Vegetated geogrid	lineal feet	Special Provision 8-19	All costs for constructing vegetated geogrid per the drawings and specs. The contracting agency will provide the live willow stakes. Measurement is per lineal foot of creek bank treated with geogrid.
13	Streambed sediment, placed	cubic yards	Spec. Prov. 9-03.11 (1)	Cost for furnishing and placing stream bed sediment in the new channel.
14	Streambed boulders, placed	each	Spec. Prov. 9-03.11 (3)	Cost for furnishing and placing stream bed boulders in the new channel.
15	Cobble grade control weir	ton	Spec. Prov. 9-03.11 (2)	Cost for furnishing and constructing the cobble grade control weir in the new channel.
16	Furnish and install Type 1 LWM habitat structures	per unit	Special Provision 8-28	Cost for furnishing materials for and constructing the Type 1 LWM pieces. Three tree trunk/root wad piece will be furnished by the contracting agency. Measurement is per unit installed.
17	Furnish and install Type 2 LWM habitat structures	per unit	Special Provision 8-28	Cost for furnishing materials for and constructing the Type 2 LWM pieces. Measurement is per unit installed.
18	Salvaged (Type 3) LWM pieces, installed	each	Special Provision 8-28	Cost for placing salvaged (Type 3) LWM pieces in the channel. Placement locations to be determined in the field by the site manager. Measurement is per log installed.
19	Rocked drainage swale	ton	9-13.1(5)	Cost for furnishing and placing 4" quarry spall for the drainage swale, measured at the quarry. Excavation of the subgrade of the swale is measured under Item No. 8 (Common Excavation).

Item No.	Item	Basis of payment	WSDOT Standard Spec. Section	Description/Specification
20	Temporary erosion and sediment control (TESC): Erosion control blanket	square yards	Special Provision 8-01.3(7)	Cost for furnishing and installing coir erosion control fabric on exposed soils on the re-graded ravine slopes.
21	TESC: straw wattle	lineal feet	8-01.3(10)	Cost for furnishing and installing straw wattle.
22	Hydroseeding all exposed soil	acre	8-01.3(2)B	Hydroseeding of exposed soil with native grass seed mix and tackifier, per acre treated.
23	Final site cleanup	lump sum		Includes removal of all temporary BMPs, temporary contractor facilities, construction boundary fencing, and trash, and any other cleanup needs at the site manager's direction.
24	Miscellaneous force account work	dollars		Amount determined by the Contracting Agency to pay for work items whose quantity is indefinite or which may vary depending on site contingencies, as determined by the site manager.


2. Bid Proposal is modified:

- 2.1 Remove Item 8
- 2.2 Renumber alternate soil disposal site to correspond with primary site bid item number
- 2.3 All remaining bid items have been renumbered accordingly.

END OF ADDENDUM No. 3A

THIS ADDENDUM MUST BE ACKNOWLEDGED BY SIGNATURE ON THE REVISED PROPOSAL PACKET DATED MAY 26, 2020

DATE OF BID OPENING: June 1, 2020 at 2:45 p.m.



Emily Derenne
Project Manager



Michael See
Natural Resource Division Manager